SECTION J – LIST OF DOCUMENTS, EXHIBITS AND OTHER ATTACHMENTS

ATTACHMENT J-8.C.3.4.3a Characteristics of Buildings/Structures for Surveillance and Maintenance Performed by the Contractor: Government Furnished Facilities for use by the Contractor

SECTION J-LIST OF DOCUMENTS, EXHIBITS AND OTHER ATTACHMENTS

ATTACHMENT J-8.C.3.4.3a Characteristics of Buildings/Structures for Surveillance and Maintenance Performed by the Contractor: Government Furnished Facilities for use by the Contractor

Facility Identification #	Property Name	Major Features	Roofing System	Year Built	Gross Sqft	Foot Print	Hours of Operation (weekly)	Total No. of Occpts	Model Bldg Type
X-108A-M	MAC Portal	South Portal and Shelter Main Drive Gate & MAC Portal	Portal – Metal Deck w/ Combustible vapor Barrier & Built-up Tar & Gravel MAC Portal – Metal Sealand Container	2012	N/A	MAC Portal 6' X 8' Indoor 40-Yard Track 180' X 27' Portal 5,508 10,030	N/A	N/A	N/A
X-108B-M	MAC Portal	North Portal and Shelter –MAC Portal	Portal – Metal Deck w/ Combustible vapor Barrier & Built-up Tar & Gravel MAC Portal – Metal Sealand Container	2012	N/A	8 x 10 330 sqft	N/A	N/A	N/A
X-108E-M1	MAC Portal	Side by Side MAC Portals (M1 and M2)	Metal - Sealand Container	2013	N/A	10' X 16'	N/A	N/A	N/A
X-108E-M2	MAC Portal	Side by Side MAC Portals (M1 and M2)	Metal - Sealand Container	2013	N/A	10' X 16'	N/A	N/A	N/A
X-108H-M	MAC Portal	Pike Avenue MAC Portal East of X-533 Switch Yard	Portal - Metal Deck w/ Combustible vapor Barrier & Built-up Tar & Gravel MAC Portal - Meatal SeaLand Container	2012	N/A	Portal 10' X 10' Shelter 5' X 15' MAC Portal 8' X 10'	N/A	N/A	N/A
X-108Q	MAC portal	North of X-151 Office Trailers	Metal - Sealand Container	2012	N/A	8’ x 10’	N/A	N/A	N/A
X-108R	MAC portal	North of X-600	Metal - Sealand Container	2012	N/A	8’ x 10’	N/A	N/A	N/A
X-108S	MAC portal	X-152J Data Center & Generator Facility	Metal - Sealand Container	2012	N/A	6’ x 8’ 6’ x 8’	N/A	N/A	N/A
X-108T	MAC portal				N/A		N/A	N/A	N/A
X-112	Data Processing Building	Shipping & Receiving location, includes 2008 Kohler Power Generator, 277/480 V, 60 Hz, 750KW, Model R1238A36	SPF (spray foam)	1980		200 X 149	40	N/A	N/A
X-152J	Data Center Trailer	Chiller- unk type, 157 tons Chiller- unk type, 157 tons Generator- 1000 KVA	Metal – Sealand Container	2012	364	364		0	MB05 MB04
X-152J-1	Data Center Chiller	Chiller- unk type, 157 tons	None	2012	N/A	N/A	N/A	0	MB04
X-152J-2	Data Center Chiller	Chiller- unk type, 157 tons	None	2012	N/A	N/A	N/A	0	MB04
X-152J-3	Data Center Generator	Generator- 1000 KVA	Metal – Sealand Container	2012	N/A	N/A	N/A	0	MB04
X-533-T2	Office Trailer	1BR, 3 fixtures	Wood Deck w/Asphalt Shingles	2005	840	840	60	1	MB01
X-533-T3	Office Trailer	1BR, 3 fixtures	Wood Deck w/Asphalt Shingles	2005	840	840	60	0	MB01
X-533-T4	Office Trailer	1BR, 3 fixtures	Wood Deck w/Asphalt Shingles	2005	840	840	60	0	MB01

Facility Identification #	Property Name	Major Features	Roofing System	Year Built	Gross Sqft	Foot Print	Hours of Operation (weekly)	Total No. of Occpts	Model Bldg Type
X-540	Telephone Building	1BR, 3 fixtures; Two 5 ton AC HVAC system; Two Steam heaters; No overhead doors	Metal Deck w/ Combustible Vapor Barrier & Built-up Tar & Gravel	1954	2,652	2,652		3	MB13
X-633-T1	Office Trailer	1BR, 3 fixtures	Wood Deck w/Asphalt Shingles	2005	840	840	60	7	MB01
X-633-T2	Break Room Trailer	1BR, 3 fixtures	Metal-Painted	2009	720	720	60	0	MB01
X-633-T3	Office Trailer	1BR, 3 fixtures	Wood Deck w/Asphalt Shingles	2005	840	840	60	7	MB01
X-700 West	Converter Shop and Cleaning Facility	Breakroom 48'X24"=1,152 sq.ft.; Office 48'X24"=1,152 sq.ft.; Office 20'X12'=240 sq.ft.; 3 Upstairs Offices 20'X20'=400 sq.ft.; 3 BR, 38 Fixtures; 4 Overhead doors ~18' high, 12' wide; Two rooftop 5 ton AC units, 2 window units	Metal Deck w/Combustible Vapor Barrier & Built-up Tar & Gravel	1954	120 x 320	38,400			MB13
X-735A	Landfill Utility Building	2BR, 7 fixtures; Office - Two electric window heating/AC units High Bay Area - Six electric heating units 2 overhead doors, both approximately 18' H x 12' W	Ribbed Metal-Painted	1981	2,820	2,820	60	12	MB03
X-744B	Salt Storage Building	Tent Stucture	Rolled Steel on Wood Deck	1979	1,000	1,000		0	MB02
X-744K	Warehouse-K		Metal	1956	35,640	35,640	60	0	MB04
X-744S-1	Salt Storage Building		Pre-engineered open span metal frame, fabric-type cover/roof system installed on concrete barricades stacked 6'high	2016	4,200	70' x 60', 36'high	60	0	
X-744Y-T1	Office Trailer	1BR, 3 fixtures	Wood Deck w/Asphalt Shingles	2005	840	840	60	3	MB01
X-744Y-T2	Office Trailer	1BR, 3 fixtures	Wood Deck w/Asphalt Shingles	2005	840	840	60	2	MB01
X-744Y-T3	Office Trailer	1BR, 3 fixtures	Wood Deck w/Asphalt Shingles	2005	840	840	60	2	MB01
X-744Y-T4	Office Trailer	1BR, 3 fixtures	Wood Deck w/Asphalt Shingles	2005	840	840	60	0	MB01
X-744Y-T5	Office Trailer	1BR, 3 fixtures	Wood Deck w/Asphalt Shingles	2005	840	840	60	2	MB01
X-744Y-T6	Office Trailer	1BR, 3 fixtures	Wood Deck w/Asphalt Shingles	2005	840	840	60	3	MB01
X-744Y-T8	Restroom Trailer	2BR, 30 fixtures	Metal-Painted	2009	720	720	60	0	MB02
X-744Y-T9	Break Room Trailer		Metal-Painted	2009	1,440	1,440	60	0	MB02
X-751	GCEP Mobile Equipment Garage		Metal	1979	35,640	35,640			
X-752AT1	Office Trailer	1BR, 2 fixtures	Metal	2000	1,440	1,440			
X-752AT2	Don & Doff Trailer		Metal	2000	1,440	1,440			
X-752AT3	Restroom Trailer	2BR, 10 fixtures	Metal	2000	800	800			
X-752AT4	Break Room Trailer		Metal	2000	1,440	1,440			
X-760-T1	Office Trailer	1BR, 3 fixtures	Wood Deck w/Asphalt Shingles	2005	840	840			
X-760-T2	Office Trailer	1BR, 3 fixtures	Wood Deck w/Asphalt Shingles	2005	840	840			
XT-801	South Office Building	Boiler System / (4) conference rooms, Dark room (microfiche)	Mineral surface/asphalt/half lap rolled	1980	223 x 100	22,300	40	N/A	N/A

Facility Identification #	Property Name	Major Features	Roofing System	Year Built	Gross Sqft	Foot Print	Hours of Operation (weekly)	Total No. of Occpts	Model Bldg Type
X-1000	Administration Building	2 Stories; 1 passenger elevator (Otis, direct hydraulic drive, 4000 lbs, 20 ft travel, machine # 602296); 3 Enclosed Stairwells; 8 BR, 44 fixtures; 65 ton closed chiller cooled AC system Recirculating Hot Water heating system Five air handlers 1 overhead door approximately 8'H x 15' W	Metal Deck w/Combustible Vapor Barrier & Built-Up Tar & Gravel	1981	73,688 30600	73,688 65,707	60	288	MB03 & MB14
X-1000S	Shelter House		Metal	2011			60		MB04
X-1000-T1	Training Trailer		Metal-Painted	2009	1,632	1,536	60	2	MB02
X-1020	Emergency Operations Center	Standby Generator, Switchgear room, three (3) restrooms	Built-Up-Roofing (Asphalt)	1985	7,180	7,180		5	N/A
X-3000	GCEP Office Building	Switchgear room	Built-Up-Roofing (Asphalt)	1985	12,447	12,447		39	N/A

MB01 - Wood, Light Frame
MB02 - Wood, Commercial and Industrial MB03 - Steel Moment Frame
MB04 - Steel Braced Frame MB05 - Steel Light Frame
MB13 - Reinforced Masny Bear Walls/Wood, Metal Deck Dphm
MB14 - Reinforced Masny Bear Walls/Precast Concrete Dphm

NOTES: 1) For X-1000, The following utilities are provided
stem from the jurisdictional boundary underground RHW lines west of the X-1000 and throughout the building. The Contractor shall be responsible for alternate heating in case of RHW failure.